

# ICC-ES Evaluation Report

ESR-4717

Reissued January 2024

This report also contains:

- CBC Supplement

Subject to renewal January 2026

ICC-ES Evaluation Reports are not to be construed as representing aesthetics or any other attributes not specifically addressed, nor are they to be construed as an endorsement of the subject of the report or a recommendation for its use. There is no warranty by ICC Evaluation Service, LLC, express or implied, as to any finding or other matter in this report, or as to any product covered by the report.



Copyright © 2024 ICC Evaluation Service, LLC. All rights reserved.

<p><b>DIVISION: 05 00 00— METALS</b></p> <p><b>Section: 05 10 00— Structural Metal Framing</b></p> <p><b>Section: 05 12 00— Structural Steel Framing</b></p>	<p><b>REPORT HOLDER: INTERPORT MAINTENANCE CO., INC.</b></p> 	<p><b>EVALUATION SUBJECT: INTERPORT STRUCTURAL BUILDING MATERIALS</b></p>	
--	--	---	---

## 1.0 EVALUATION SCOPE

### 1.1 Compliance with the following codes:

- 2021 and 2018 [International Building Code® \(IBC\)](#)
- 2021 and 2018 [International Residential Code® \(IRC\)](#)

### Property evaluated:

- Structural - Materials

### 1.2 Evaluation to the following green code(s) and/or standards:

- 2022 [California Green Building Standards Code \(CALGreen\)](#), Title 24, Part 11
- 2020, 2015, 2012 and 2008 [ICC 700 National Green Building Standard™](#) (ICC 700-2020, ICC 700-15, ICC 700-2012 and ICC 700-2008)

### Attributes verified:

- See Section 3.1

## 2.0 USES

Interport structural building materials are used in custom designed, factory built, building modules transported to the jobsite to construct site specific buildings.

## 3.0 DESCRIPTION

Interport Shipping Container Structures are site-specific, custom-designed, factory-built modules. The modules are transported to the jobsite and assembled to form a completed building. Shipping containers are used as the source of structural and non-structural building materials for constructing the modules. The steel structural building materials from the shipping containers and the quality control process for selecting shipping containers are the subject of this report. All other aspects of the modules are outside the scope of this report. The steel components of the shipping containers selected for use as structural building materials have been correlated to the appropriate ASTM International steel specification, and are suitable for use with the design provisions specified in the American Institute of Steel Construction Specification for Structural Steel Buildings (AISC 360) or the American Iron and Steel Institute North American Specification for the Design of Cold-Formed Steel Structural Members (AISI S100), as applicable. The various components used, detail drawings of the

components, steel specification for the steel used to fabricate the components, cross-reference to the equivalent ASTM standard, yield strength, and tensile strength used for design are specified in the following Interport Technical Specifications.

The attributes of the containers have been verified as conforming to the provisions of (i) CALGreen Section A4.404.3.3 and (ii) ICC 700-2020, ICC 700-15 and ICC 700-2012 Section 601.5 and 11.601.5; and (iii) and ICC 700-2008 Section 601.5 for prefabricated structural components. Note that decisions on compliance for those areas rest with the user of this report. The user is advised of the project-specific provisions that may be contingent upon meeting specific conditions, and the verification of those conditions is outside the scope of this report. These codes or standards often provide supplemental information as guidance.

## 4.0 DESIGN AND INSTALLATION

The structural building materials used in the building modules must be designed in accordance with the AISC 360 or AISI S100, as applicable. The design of the building module must be in compliance with the IBC, and installation of the building modules must be in accordance with the approved plans. The approved plans must be available at the jobsite at all times.

## 5.0 CONDITIONS OF USE:

The Interport structural building materials described in this report comply with, or are suitable alternatives to what is specified in, those codes listed in Section 1.0 of this report, subject to the following conditions:

- 5.1 The scope of this report is limited to the evaluation (verification) of the steel structural building materials used in construction of the building modules in the Interport Maintenance facility for their suitability for use with AISC 360 and AISI S100. All other aspects of the building modules and the final structure, such as, (but not limited to,) structural design, plumbing and electrical are outside the scope of this report.
- 5.2 Where approved by the code official, the marks and existing data plates on the intermodal shipping containers are permitted to be removed before they are repurposed for use as buildings or structures or part of buildings or structures in accordance with Section 3115.3 of the 2021 IBC.
- 5.3 The design of buildings or structures with repurposed intermodal shipping containers conforming to ISO 1496-1 shall be in accordance with Section 3115.8 of the 2021 IBC.
- 5.4 Complete construction documents and calculations must be submitted to the code official for each specific project. The calculations and construction documents must be prepared and sealed by a registered design professional where required by the statutes of the jurisdiction in which the project is to be constructed.
- 5.5 A copy of this report must be submitted in addition to all other required material when applying for a building permit.
- 5.6 The structural building materials are procured for use in the Interport Maintenance Co., Inc. facility in Newark, New Jersey, under quality control programs with inspections by ICC-ES.

## 6.0 EVIDENCE SUBMITTED

Data in accordance with the [ICC-ES Acceptance Criteria for Structural Building Materials from Shipping Containers \(AC462\)](#), dated October 2018 (editorially revised March 2021).

## 7.0 IDENTIFICATION

- 7.1 Each Interport Shipping Container Structure manufactured from shipping container materials shall be labeled with the Interport Maintenance Co., Inc. name and address, and the evaluation report number (ESR-4717).
- 7.2 The report holder's contact information is the following:

**INTERPORT MAINTENANCE CO., INC.**  
**635 DELANCY STREET**  
**NEWARK, NEW JERSEY 07105**  
**(973) 508-1612**  
[www.iport.com](http://www.iport.com)

**DIVISION: 05 00 00—METALS****Section: 05 10 00—Structural Metal Framing****Section: 05 12 00—Structural Steel Framing****REPORT HOLDER:****INTERPORT MAINTENANCE, INC.****EVALUATION SUBJECT:****INTERPORT STRUCTURAL BUILDING MATERIALS****1.0 REPORT PURPOSE AND SCOPE****Purpose:**

The purpose of this evaluation report supplement is to indicate that Interport structural building materials, described in ICC-ES evaluation report ESR-4717, have also been evaluated for compliance with the codes noted below.

**Applicable code editions:**

- 2019 *California Building Code* (CBC)

For evaluation of applicable chapters adopted by the California Office of Statewide Health Planning and Development (OSHPD) AKA: California Department of Health Care Access and Information (HCAI) and the Division of State Architect (DSA), see Sections 2.1.1 and 2.1.2 below.

- 2019 *California Residential Code* (CRC)

**2.0 CONCLUSIONS****2.1 CBC:**

The Interport structural building materials, described in Sections 2.0 through 7.0 of the evaluation report ESR-4717, comply with CBC Chapter 22, provided the design and installation are in accordance with the 2018 *International Building Code*® (IBC) provisions noted in the evaluation report and the additional requirements of CBC Chapters 16, 17 and 22, as applicable.

**2.1.1 OSHPD:**

The applicable OSHPD Sections and Chapters of the CBC are beyond the scope of this supplement.

**2.1.2 DSA:**

The applicable DSA Sections and Chapters of the CBC are beyond the scope of this supplement.

**2.2 CRC:**

The Interport structural building materials, described in Sections 2.0 through 7.0 of the evaluation report ESR-4717, comply with CRC Chapter 3, provided the design and installation are in accordance with the 2018 *International Residential Code*® (IRC) provisions noted in the evaluation report and the additional requirements of CRC Chapter 3, as applicable.

This supplement expires concurrently with the evaluation report, reissued January 2024.